

## Birchview Road Pedestrian Walkway (Location #694 – Blind Curve)

Prepared by: Thomas Tooke/Tooke Construction Services Inc.

ITEM	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	TOTAL
<b>1.00</b>					
1.1	Mobilize/Demobilize	LS	1	\$600.00	\$600.00
1.2	Sediment Control	LS	1	\$900.00	\$900.00
1.3	Testing and Inspection	LS	1	\$600.00	\$600.00
1.4	Traffic and Pedestrian Control	LS	1	\$3,500.00	\$3,500.00
1.5	Dust Control	LS	1	\$250.00	\$250.00
				<b>Item Total</b>	<b>\$5,850.00</b>
<b>2.00 Removals</b>					
2.1	Saw Cutting – If required	M	165	\$5.00	\$825.00
2.2	Surplus Material	M3	70	\$12.00	\$840.00
2.3	Rock Removal	M3	0	\$0.00	\$0.00
2.4	Tree Clearing/Trimming	LS	1	\$250.00	\$250.00
				<b>Item Total</b>	<b>\$1,915.00</b>
<b>3.00 Pedestrian Walkway (1.20m) Width</b>					
3.1	Equipment and Labour	HR	38	\$600.00	\$22,800.00
3.2	2" Limestone Crusher Run	Tonne	170	\$16.00	\$2,720.00
3.3	3/4" Limestone Crusher Run (200mm Thickness)	Tonne	90	\$17.00	\$1,530.00
3.4	Screened Topsoil	Tonne	90	\$23.00	\$2,070.00
				<b>Item Total</b>	<b>\$29,120.00</b>
<b>4.00 Signage/Line Painting</b>					
4.1	No Parking/Pedestrian Walkway	LS	1	\$600.00	\$600.00
4.2	Line Painting/Centre Line	LS	1	\$800.00	\$800.00
				<b>Item Total</b>	<b>\$1,400.00</b>
<b>Sub Total</b>					<b>\$38,285.00</b>

## **Birchview Road Pedestrian Walkway (Location #694 – Blind Curve)**

**NOTES:** The following estimate includes all labour, equipment and materials for the construction of a 1.20m wide pedestrian/cyclist pathway along both sides of Birchview Road on the blind curve at address #694.

The length of the pathway along the north side (inside corner) is approximately 65.00m in length, excluding the two entrances At 694.

The length of the pathway along the south side (outside corner) is approximately 100.00m in length and will span between the hydro pole from the East to the hydro pole to the West.

The depth of granular material makeup for the pathway is as follows:

- 300mm Granular 'B'
- 150mm Granular 'A'